

साहेबगंज महाविद्यालय, साहेबगंज



SAHIBGANJ COLLEGE, SAHIBGANJ

(A Constituent unit of Sido-Kanhu Murmu University, Dumka)

NAAC Accredited (Grade-B) - MODEL COLLEGE

शिक्षा संकाय (बी.एड.)



Office of the Principal
Sahibganj - 816109 (Jharkhand)

Tel No - 06436-222056 (O)
Email Id : principal@sahibganjcollege.in
Website - www.sahibganjcollege.ac.in
Fax No : 06436-222056

Ref./Letter No : B.EA/115/2025

Date : 18-03-2025


निविदा आमंत्रण सूचना अति अल्पकालीन निविदा

साहेबगंज महाविद्यालय के बी०एड० भवन (M.S.D.P) Block में इच्छुक आपुतिकर्ता एवं अग्नि सुरक्षा कार्य करनेवाले फर्म से सीलबंद लिफाफा में निविदा आमंत्रित करता है। इच्छुक निविदाताओं को सूचित किया जाता है कि सीलबंद लिफाफा में प्राचार्य, साहेबगंज महाविद्यालय, साहेबगंज को दिनांक 25.03.2025 संध्या 5 बजे तक प्राचार्य कार्यालय साहेबगंज में समर्पित किया जा सकता है।

अग्नि सुरक्षा कार्य होने वाले भवन का विवरण इस प्रकार है।

1. बी०एड० भवन G+2 मंजिल है। कुल भवन का निर्माण क्षेत्रफल – 25387 sq.ft
2. 15 कमरे का आकार (प्रति कमरा) 30'X25.4" approx.
3. 3 कमरे का आकार (प्रति कमरा) 33'X41' approx.
4. 3 छात्रों का शौचालय 21'X9'
5. छात्राओं का शौचालय 21'X9'

संदर्भित सूचना महाविद्यालय के वेबसाइट एवं महाविद्यालय के सूचना पट से प्राप्त किया जा सकता है।


प्राचार्य 18/3/2025

Continued


साहेबगंज महाविद्यालय साहेबगंज
18/3/25

नोट- अपरिहार्य स्थिति उत्पन्न होने पर निविदा को निरस्त करने का अधिकार प्राचार्य के पास सुरक्षित है

आपूर्ति किए जाने वाले समान का विवरण एवं बी०एड भवन में स्थापित करने संबंधी सामग्री की सूची निम्नांकित है।

Sl.no	ITEMS	QTY
1.	Supplying of 100 mm dia MS 'B' Class pipe with companion Nut Bolt, Flange, Short Band, Packing and Signal Red Colour. As per IS: 1239 (Make: Zindal/Tata).	142 MTR
2.	Supplying of 80 mm dia MS 'B' Class pipe with companion Nut Bolt, Flange, Short Band, Packing and Signal Red Colour. As per IS: 1239 (Make: Zindal/Tata).	12 MTR
3.	Supply & installation of ISI marked single headed 63 mm dia. Hydrant Valve, 80 mm dia flanged inlet with 63 mm female instantaneous outlet conforming to IS: 5290 on the fire wet riser/down comer, including making 80 NB pipe connection with riser, fixing the landing valves in proper positions, Including supply of nuts, bolts, gaskets, caps, chains etc. testing the hydrant and completing the work in all respect as per directions of the Engineer-in-Charge. (Make: Safe Pro).	14PCS
4.	Supplying & Installation of Two Way Inlet Valve Complete. (Make: Safe Pro).	1PCS
5.	Supplying & Installation of fire hose box single door cabinet outdoor, MS sheet having glassed hinged door The words "FIRE HOSE" to be painted on the box. (Make: Safe Pro).	12 PCS
6.	Supplying & Installation of First Aid Hose Reel Drum Complete with 30 Mtrs. Hose. (Make: Safe Pro).	12 PCS
7.	Supplying of ISI marked RRL (IS: 636, type-A) fire hose pipe 15 meter long and 63 mm dia with ISI marked (IS: 903) Stainless steel male and female coupling bound and rivetted to hose pipes with copper rivets and copper wire complete as required. (Make: Safe pro).	12 PCS
8.	Supplying of 63 mm dia Short Branch Pipe SS. IS:903 (Make: Safe Pro).	12 PCS
9.	Supplying & Installation of 25mm Ball Valve. (Kartar)	12 PCS
10.	Supplying & Installation of 100 mm dia Butterfly Valve. (Make: Kartar)	1 PCS
11.	Supplying & Installation of 100 mm NRV. (Kartar)	1 PCS
12.	Supplying & Installation of (900 LPM-KDI-10 HP-3PH) Terrace Pump Motor (Make: Kirloskar)	1 PCS
13.	Supplying & Installation of Starter for terrace Pump.	1 PCS
14.	Supplying & Installation of Pressure Guage. Donfas	1 PCS
15.	Supplying & Installation of 3cx2.5 ² mm Cable. Fire guard	40 MTR
16.	Supplying & Installation of MCP. (Make: Agni).	10 PCS
17.	Supplying & Installation of Hooter. (Make: Agni).	10 PCS
18.	Supplying & Installation of Alarm Panel 4 Zone. (Make: Agni).	1 PCS
19.	supplying & Installation 1 Core Wire with Conduit	1 PCS
20.	Supplying & Installation of PVC 3 layer Water Tank 10,000 Litters (ISI)	1 PCS
21.	ABC Fire Extinguisher-6 Kg (safe Pro)	12 PCS
22.	CO2 Type Fire Extinguisher-4.5 Kg (safe Pro)	7 PCS

Note- Rate to be provide with complete Installation including Labour charge, Plumbing work and Transportation.



प्राचार्य

+

साहेबगंज महाविद्यालय साहेबगंज